NOTES:

- 1. OPERATION TYPE MAY BE PUSH-UP, HAND CHAIN OR ELECTRIC.
- 2. FOR CRITICAL FITS DUE TO REDUCED AVAILABLE HEADROOM OR SIDEROOM CLEARANCES, CONSULT
- 3. CLEARANCES SHOWN ARE MAXIMUMS. LESSER CLEARANCES MAY BE POSSIBLE.
- 4. UNLESS OTHERWISE NOTED, DOORS SHALL BE PROVIDED WITH SLIDE LOCKS AT EACH END OF BOTTOM BAR, ENGAGING GUIDES IN THE LOCKED POSITION.
- 5. ALL OPENING PREPARATION, ELECTRICAL POWER AND FIELD PAINTING SHALL BE PROVIDED BY OTHERS.

SLIDE LOCK-

- 6. SERIES 190HDI IS AN INSULATED SERIES 190HD.
- 7. CURTAIN FINISH SHALL BE SILICONE POLYESTER PRE-PAINT OVER GALVANIZED GRADE 80
- 8. GUIDES, BRACKETS, BOTTOM BAR ANGLE AND HEAD STOPS ARE ZINC COATED.


CONCRETE/MASONRY: POWERS WEDGE-BOLT, 3/8 X 1 3/4" LONG


9. MAXIMUM OPENING SIZE: 12'-0" X 14'-0".


WOOD: LAG SCREW, 3/8 - 7 X 3" LONG


END VIEW

BRACKET ATTACHMENT










12 GA GUIDE MOUNTING DETAIL


7"
7 ½"
8 ½"
BARREL ASSEMBLY

(*) FOR PUSH-UP OPERATION.....6"



HEADROOM REQUIRED

OPENING HEIGHT	VERTICAL HEADROOM	HORIZONTAL HEADROOM
THRU 8'-0"	19"	19"
OVER 8'-0" THRU 10'-0"	20"	20"
OVER 10'-0" THRU 14'-0"	20 ½"	20"



COMMERCIAL DOOR SERIES: 190HD/190HDI

CUSTOMER NUMBER:	DATE:
CUSTOMER NAME:	CONTACT:
PRO JECT NAME:	

PROJECT LOCATION:

BOTTOM BAR ASSEMBLY

DRAWING NUMBER:

PLANT:

DRAWN BY:

DATE: SHT: OF: **ASTAAMERICA** BY JANUS INTERNATIONAL

SALESPERSON:

JAMB TYPE OPERATION WEATHERSTRIP DOOR SERIES OPENING SIZE OUTSIDE OPERATION CURTAIN | PUSH | ORDER ADDED OPTIONS CONC./ REDUCED HAND ELECTRIC STEEL WOOD TOP | HEADER | SIDE NUMBER COLOR 190HD 190HDI WIDTH | HEIGHT MAS.

INSIDE ELEVATION